

# Wimmera Project Noise and Vibration Impact Assessment

A. 8. 9. 2.

Community Information Session 24 March 2021

# **Noise and Vibration Impact Assessment**



Noise and Vibration Assessment Objectives



Measurement of Existing Conditions



Criteria



**Impact Assessment** 



# **Noise and Vibration – EES Draft Evaluation Objective**

- To protect the health and wellbeing of the community, and minimise effects on air quality, noise and social amenity.
- Assess the likely noise increases, and vibration impacts at sensitive receptors in the vicinity of the project and along the proposed transport route.

# **Noise and Vibration – Key legislation and guidance**

#### **Construction**

#### State

• *Civil construction, building and demolition guide* (EPA Vic Publication No. 1834)


#### Vibration (No applicable AS/NZ standards)

- BS6472-1: 2008 Guide to evaluation of human exposure to vibration in buildings.
- DIN 4150 Part 3. Structural Vibration in Buildings – Effects on Structures

#### **Operation**

#### State


- Environmental Protection Act 1970 (Vic)
- Environmental Protection Amendment Act 2017 (Vic) (from July 2021)
- Noise from Industry in Regional Victoria (EPA Vic Publication No. 1411) (NIRV)
- Road Noise Policy, NSW (2011)



# Mine layout and closest receptors

- Sensitive receptors in all directions surrounding the mine site.
- Noise levels modelled for all sensitive receptors within 5km of the mine site including, Noradjuha, Toolondo and Clear Lake.
- Six receptors within mine layout development envelope will require an access agreement; R1, R2, R3, R4, R5, R37.

AECOM



# **Baseline noise monitoring**

Period	Average L <sub>A90</sub> dB	
Day	27 to 34	
Evening	26 to 32	
Night	21 to 25	

- Noise monitoring in February 2019 for one month at six locations.
- Further monitoring in March 2020 at three locations.
- Typical noise levels for rural environment.

### R119 R28 Site 2 R36 R27 R4 Jallumba-Mockinya Road E2 R3 Site 1 Legend Receptors R2 **R1** Vibration Monitoring ocations

# **Baseline vibration monitoring**

- Site 1 Natimuk-Hamilton Road
- Site 2 Nurrabiel Church Road


Measured existing vibration levels are low, and below human comfort vibration criteria for a residential building.

## **Construction noise and vibration assessment**

- Construction works will occur predominantly during normal (daytime) working hours, for a period of up to two years.
- Construction activities located primarily at northern end of the mine site.
- There are no noise criteria for construction works during normal working hours.
- Some stages will occur concurrently.
- Vibration will not be an issue at receptors more than 200 metres away.

Stage	Activity	Duration	Description
C1	Bulk/earthworks/civils	2 months	Clearing and preparing site, excavations
C2	Concrete works	4 months	Establishing concrete platforms for the proposed infrastructure.
C3	Mine access road	2 months	Preparation, surfacing works, excavation and road profilers.
C4	Plant construction	12 months	Installation of processing plant and associated large infrastructure
C5	Floc Plant/SMP install	12 months	Installation of the flocculent plant, structural, mechanical and piping within the processing plant area
C6	Evaporation pond and tailings storage facility	3 to 4 months	Ground preparation, excavation, construction of the evaporation ponds, tailings storage facilities.

#### **Construction noise assessment**



#### **Operational noise assessment**

Noise from Industry in Regional Victoria (NIRV) Publication 1411 Recommended Maximum Noise Levels (RMNLs)



- Noise model includes mining fleet, processing plant, and other ancillary equipment including truck movements
- Fixed location of mineral unit plant (MUP)
- Noise levels modelled by Years 1, 7, 13, 16, 17 and 19
- Noise modelling is an iterative process to assess mitigation options
- Modelled levels are compared the NIRV Recommended Maximum Noise Levels

# **Operation - Initial mitigation measures**

- Dredge mining method
- Fixed location of mineral unit plant (MUP)
- Stockpiles
- AMC cell activity day period only
- Reduced night time ancillary and mining activities







Amphiroller in the Accelerated Mechanical Consolidation (AMC) cell


#### **Operational noise assessment Year 1**





#### **Operational noise assessment Year 16**





# **Key findings - Operation**

#### Night-time mining


Operational noise is predicted to exceed the NIRV Recommended Maximum Noise Level (36 dB(A))

- Red exceedance > 7 dB
- Yellow exceedance < 7 dB
- Blue exceedance <2 dB

Exceedances in the north primarily due to the processing plant, elsewhere primarily due to the mining fleet.


Further noise mitigation measures should be investigated to reduce the noise impacts from:

- Ancillary mobile mining plant and overburden activities.
- Mineral processing plant and facilities.



## **Noise and vibration assessment - Transport Route**

- Four transport route options under consideration.
- 60 truck movements per 24-hour period, (2 to 3 movements per hour).
- Assessment to consider the noise impacts and potential for sleep disturbance at receptors within 100 metres from the road.
- Option 3, north along the Natimuk-Hamilton Road, has the most sensitive receptors <100 metres (20 receptors).</li>
- Mitigation measures may be required to reduce noise impacts.
- Vibration from trucks will not be an issue on maintained road surfaces.
- Further studies required once option selected.



#### **Next steps - development of mitigation measures**

- Consultation with the local community to discuss the noise and vibration impact assessment.
- Discussions with the EPA, council and stakeholders.
- Refinement of proposed operations and mitigation measures to satisfy the evaluation objectives set out in the EES scoping requirements.
- Consult with individual landowners regarding the predicted noise impacts at their properties and associated potential mitigation options.
- Development of a noise measurement and event response plan.
- Documentation of how the Project will effectively implement and manage the environmental performance during construction and operations.